

## Annex 18 Performance Warranty Schedule

**La Vendimia Solar Installation** 

Sandies.

## 1. Provisional Acceptance Test (PAT)

Year 0	Theoretical Performance Ratio	Guaranteed Performance Ratio	T <sub>mod</sub> [°C]
Jan	78.09% 76.14%		43.13
Feb	83.20%	81.12%	42.40
Mar	86.90%	84.73%	37.52
Apr	90.40%	88.14%	31.55
May	92.68%	90.36%	23.99
Jun	93.96%	91.61%	19.92
Jul	94.01%	91.66%	20.41
Aug	93.62%	91.28%	21.76
Sep	90.96%	88.69%	27.58
Oct	85.69%	83.55%	31.74
Nov	81.61%	79.57%	37.25
Dec	80.31%	78.30%	41.23
Year 0	85.09%	82.96%	-

For the avoidance of doubts, the Guaranteed PR is equal to 97.5% of the Theoretical PR. Minimum PR is equal to 92% of the Theoretical PR.

## 1. Intermediate and Final Acceptance Test (IAT and FAT)

Year	Test	Theoretical Performance Ratio	Guaranteed Performance Ratio	Annual Degradation	Minimum PR
1	IAT	84.94%	84.94%	0.25%	78.14%
2	FAT	84.65%	84.65%	0.35%	77.88%